राष्ट्रीय राजधानी क्षेत्र दिल्ली सरकार
GOVT. OF NATIONAL CAPITAL TERRITORY OF DELHI
लोक निर्माण विभाग
PUBLIC WORKS DEPARTMENT
कार्यालय अधीक्षण अभियंता (के.एवं.न.दि.परि.)
OFFICE OF THE SUPERINTENDING ENGINEER (C&ND-C)
रिंग रोड बाईपास फलोईओवर के नीचे,
UNDER RING ROAD BYE-PASS FLYOVER
विपरीत आई.जी.आई स्टेडियम गेट नं. 9
OPPOSITE IGI STADIUM GATE NO. 9
नई दिल्ली–110002.
NEW DELHI-110002.
Phone : 011-21400871
E-Mail: sepwddelhicnd@gmail.com

No. 23(106)/SE/C&ND Circle/PWD/2026-27/1346 (E) Date : 3/06/2026

Office Memorandum

Sub.: Preparation of coming monsoon season.

It is well known that monsoon season starts from last week of June and onward in Delhi. In order to tackle the problem of water logging in Delhi during rainy season, efficient and timely cleaning of drains and functioning of pumps etc. are of paramount importance.

In this regard, the following directions are issued:-

A:- Drain Cleaning:-

1. Cleaning of drains should start immediately now and onward & it shall be ensured that all drains are properly cleaned by **15.06.2026**, i.e. well before the onset of monsoon.
2. Proper evidences in the form of photographs/videos in support of drains having been cleaned, should be maintained.
3. Silt extracted from the drains should be cleared within 24 hours so that the extracted silt do not enter into the drain again.
4. The PWD drains which are having its outfall in the drains/nallahs of other department, may be identified and it should be ensured that outfall of PWD drains should be cleaned periodically on regular basis by the concerned department. The concerned SEs are required to take up the matter with the concerned MCD, DJB, I&FC etc. authorities to clean the drains under their charge on regular basis.
5. It should be ensured that all manhole are properly covered so as to avoid any chance of accident during the rainy period. **All the EEs shall submit a certificate to this effect to their SEs/CEs and Nodal Officer by 15.06.2026.**

6. It should be ensured that bell mouth on road sides as well as rain water pipes of flyovers are cleaned properly. This exercise shall be repeated on regular basis during the monsoon period.

B. Maintenance of Pumps:

1. Concerned EEs (Elect.) shall ensure that all the installed pumps are functional and sumps are desilted properly and **a report to this effect be submitted to their CEs through SEs by 15.06.2026**. Superintending Engineers as per details given below shall inspect the pumps of other circles & submit their report by **17.06.2026** in enclosed Performa.

S. No.	Name of Circle	Pumps to be checked by SE
1	South-West	South
2	South-East	South-West
3	South	South-East
4	North	West
5	North-West	North
6	West	North-West
7	East	C&ND
8	North East	East
9	Shadara	East
10	Central & New Delhi	Shahdara
11	Project	North-East

03/06/26
(कृष्ण कुमार सिंह)
अधीक्षण अभियंता
Nodal Officer
(Monsoon Preparedness)

Copy for information to (through e-mail):
1. The Pr. Secretary, PWD, GNCTD, 3rd Floor, MSO Building, New Delhi
2. The Engineer-in-Chief, PWD, GNCTD, New Delhi
3. The Pr. Chief Engineer (M&F), PWD, GNCTD, New Delhi.
4. The Chief Engineer (South), PWD, 7th Floor, MSO Bldg, New Delhi.
5. The Chief Engineer (North), PWD, 5th Floor, MSO Bldg, New Delhi.
6. The Chief Engineer (East), PWD, 3rdth Floor, MSO Bldg, New Delhi.
7. All SEs under Maintenance Zone, PWD GNCTD, New Delhi.

03/06/26
(कृष्ण कुमार सिंह)
अधीक्षण अभियंता

Inspection of Report of Pump & Sumps

1. **Zone**
2. **Circle**

Sl. No.	Division	Location of		Status of Pumps				Status of Sumps			
		Pumps	Sumps	No. of Pumps	Capacity of Pumps	Working	Not Working	Capacity (Cum)	Desilted / to be desilted	Target, if not desilted	Remarks

(कृष्ण कुमार सिंह)
अधीक्षण अभियंता
Nodal Officer
(Monsoon Preparedness)